



SURAT MUNICIPAL CORPORATION

Surat Sitilink Limited

Name of Work: -Supply, Installation , Testing & Commissioning (SITC) of Tube light fixtures/ Ballast/only Tube for various bus shelters on Udhana - Sachin Corridor.

Issue Start Date : - 08/01/2021 from
11.00 AM

Last Date of Issue : - 15/01/2021 up to
06.00 PM

Last date of Submission : - 22/01/2021 up to
05.00PM

-:Submitted to: -

The Chief Accountant

Surat Municipal Corporation

Muglisara, Surat-395003

SITILINK/Out/No: 1308

Date: 08/01/2021

Sd/-

Executive Engineer,

& General Manager (Engg- SSL),

Surat Municipal Corporation



Surat Sitalink Ltd
Room no.95, 2nd floor
Surat Mahanagar Sevasadan
Muglisara,
Surat-395003

Quotation for Supply, Installation, Testing & Commissioning (SITC) of Tube light fixtures/ Ballast/ Tube light rod (only tube)for various bus shelters on Udhana - Sachin Corridor

To
Executive Engineer &
General Manager (Engg- SSL)
Surat Sitalink Limited,
Room no 95-96,
Surat Municipal Corporation
Mugalisara - Surat-395003

Dear Sir,

Surat Sitalink Ltd. Invites Quotation for Supply, Installation , Testing & Commissioning (SITC) of Tube light fixtures/ Ballast/ Tube light rod(only tube) (including Buy back) for various bus shelters on Udhana - Sachin Corridor items @ not exceed than 1,99,000 or 1 (one) year whichever is earlier on annual rate contract (ARC) from various Electrical Contractors at Surat Sitalink Limited. Following are the details.

Sr no	Product Specifications (As installed in bus shelters) (Detail specifications are attached herewith)	Unit (Nos/Mtr)	Rate of Buyback (existing nonfunctional) per unit (A)	Rate Inclusive of all taxes, labour, levies, etc/ per unit (B)	Rate with All Taxes, labours / per Unit (C) = (B) - (A) (Inclusive of all taxes, labour, levies, etc)
1	SITC of 1x 14 watt T5 tube Light fixture 20 to 300 V, Power Factor more than 0.9, CCT 4000 K Uniformity ratio >0.7,CRI >85 Luminaire efficacy> 84 lumens/watt (rated) , efficiency > 85 %	Nos			
2	SITC of only 14 watt tube Power Factor more than 0.9, CCT 4000 K Uniformity ratio >0.7,CRI >85 Luminaire efficacy> 84 lumens/watt (rated) , Efficiency > 85 %)				
3	SITC of only Ballast/Choke/Driver for 14 watt T-5 Tube light fixture matching and working with tube light with Sr no 1 and 2				
4	SITC of 1x 28 watt T5 tube Light fixture 20 to 300 V, Power Factor more than 0.9, CCT 6000 K Uniformity ratio >0.7,CRI >85 Luminaire efficacy> 84 lumens/watt (rated) , efficiency > 85 %				
Total (in words)					

Note:-

1. Contractor has to visit the Site and check all conditions and installed apparatus installed at bus shelters before filling Quotation invited for. No excuse will be accepted afterward.
2. Proposer Must Submit Demand Draft of Rs. 672.00 as Quotation fee in the favor 'Surat Sitalink Limited' with submission.

3. Proper Must Submit Demand Draft of Rs. 2000.00/- as Earnest Money Deposit (EMD) in the favor 'Surat Sitalink Limited'. EMD will be return to unsuccessful proposer after assigning work to L1 bidder.
4. The Quotation is to be sent in the name of 'Chief Accountants', Surat Municipal Corporation, Gordhandas Chokhawala Marg Mugalisara , Surat-395003 , in Sealed Envelope on or before 22/01/2021 up to 17.00 Hrs by speed Post/RPAD only.
5. Quoted Rate will be valid for 12 months and Surat Sitalink Limited may order more quantity on the approved rate.
6. Contractor has to quote rate per unit only and total rate will be considered for deciding L1 bidder.
7. Electrical Contractor must have valid Electrical contractor license.
8. The scope of work includes removing of existing nonfunctional T-5 tube light fixtures/Ballast/Tube only and Supply, Installation, Testing & Commissioning (SITC) of T-5 Tube light fixtures/ Ballast/ Tube light rod (including Buy back). Contractor has to check non-working Light fixture with Tube rod/ ballast and then proceed further for replacement (if require) of entire fixture however work must be carried out work in presence of Sitalink representative and prepare Joint Measurement Report (JMR) and according to that payment will be given. Contractor has to inform Sitalink representative before installation of work. **Product must be covered with 02 year replacement guarantee.**
9. **No Advance Payment will be given. 95 % Payment will be given after successful completion of work and 05 % Payment will be released after 06 months subject to satisfactory work.**
10. The awardee agency has to complete work within 20 days (Twenty) of work order given. Any delaying beyond this tends to apply penalty Rs. 500 /- day of delaying.
11. Delaying in submission of the quotation will not be considered.
12. **Contractor must follow technical specifications as per attachment, submission of warranty certificates and bill /challan.**
13. Successful awardees agency has to enter in to the agreement of 300 Rs Stamp paper and submit Demand Draft of Rs. 10,000 /- in the favor of 'Surat Sitalink Limited' as performance security within 10 days, failing to which penalty @ 0.065 % per day of delay of Performance Security amount .
14. Surat Sitalink Ltd has right to change quantity in ± 30 % of quantity. It may reduce or offer order for more quantity on the basis of approved rate in the future.
15. Surat Sitalink Ltd Reserves the right to accept or reject any or all the quotations received without assigning any reasons thereof.
16. Above Quantity may changes during survey due to any circumstances and order will be given as per requirement only.
17. List of bus shelters with quantity, brand list are attached here with. Quantity may vary during survey and payment will be given on actual work to be performed.

Sd/-

Executive Engineer (BRTS)&
General Manager (Engg -SSL)

Dt: / /2021
Surat

Name of Proposer

Sign & Stamp of Proposer

Address of Proposer:—

Mobile: no:-

Item	List of approved make
Tube Fixture/Tube	Philips, Osram, Any other similar to category -III of Prevailing SOR
Ballast/Driver/Ballast	Philips, Osram, Any other similar to category -III of Prevailing SOR

Above specification are indicative and Contractor must follow above specifications and ensure that technical specifications must be maintained.

List of Bus shelters with Quantity :-

Sr no	Bus shelter	Only Tube	Choke/Ballast	Tube light fixture
1	Satyanagar	18	8	20
2	Udhana Teen Rasta	16	4	34
3	Udhna GSRTC	19	8	22
4	Udhana Academy	12	4	8
5	Laxminarayan Temple	12	8	18
6	Pandesara GIDC	10	15	15
7	Kaamnath Mahadev	8	10	17
8	Navin Florine	8	12	18
9	Bhestan Naher	10	11	22
10	Bhagavatinagar Industrial Estate	11	7	19
11	unn naka	15	12	20
12	unn industrial estate	10	8	19
13	unn char rasta	11	10	16
14	Green Park	12	9	6
15	Sachin GIDC	18	10	16
	TOTAL	190	136	270